

LISTA CANTITATI

MATEC CNC TEHNIC - INFRASTRUCTURA

N R. C RT	COD/ DENUMIRE	U.M/ CANTITATE MATERIAL		PRET MATER. / MANOP ./ UTIL.(tr ansp)	MATERI AL (MAT.)	MANOPE RA (MAN)	UTILAJ TRANS- PORT (UT +TRA)	TOTAL
1	TSC02D1 Decopertare strat vegetal ,pretul cuprinde spatul si transportul pamantului la 5 km	mp	2700					
2	DA06A1 Compactare pamant cu rulou compactor	mp	2700					
3	01007A Strat separatie geotestil	mp	2700					
4	DA06B1 Stat de balast 40 cm	mc	1080					
5	ASIMILAT Fundatie marginala F1 Pretul include spatura,cofraje,betonC16/20- 7,2mc otel PC52-365kg pe o fundatie	buc	16					
6	ASIMILAT Fundatie centrala F2 idem F1 cu mentiunea betonC16/20- 5,8mc,otelPC52-290 kg	buc	8					
7	ASIMILAT Fundatie de fronton F3 idem F1 cu mentiunea beton C16/20-3,4 mc,otelPC52-170 kg	buc	10					
8	ASIMILAT Grinda de fundare perimetrala si soclu(+30),pretul cuprinde toate lucrarile,sapatura,cofraje,betoa ne si decofrare betonC20/25si otelPC52 5760kg	ml	182,4					
9	CL03B Pozitionare si montare carcase cu buloane ancoraj	kg	790					

10	DA06A1 Umplutura compactata in jurul fundatiilor	mc	307					
11	01007A Procurare si montare folie polietilena sub pardoseala	mp	2304					
12	CA01A Armare cu plasa sudata Dn6mm cuochiri 100x100 mm	kg	11770					
13	CA02I1 Pardoseala de tip industrial in grosime de 22 cm elicoptrizata si 5 kg cuart	mp	1970					

Beneficiar